BRUHAT BANGALORE MAHANAGARA PALIKE, YALAHANKA ZON

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

Draft SCHEDULE-B

Issued to :

Original / Duplicate
Item No.

Name of Work : Improvements to Roads, Drains and Asphlting to Roads in Venkategowda layout Kempapura 1st A Main in ward no. 7, Byatarayanapura in Kodigehalli sub division

Sl. No	Approved Quantity	Description	Unit	Sanctioned Rates In Figures
1	1597.20	Removing BS Slab of drain and stacking.	Sqm	44.47
2	1277.76	Refixing stone slabs of drains and pointing in CM 1:3.	Sqm	63.00
3	319.44	Providing granite slabs of selected quality roughly	Sqm	315.36
4	580.80	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	Cum	58.32
5	3872.00	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (167, I.No. 19.64) SR 2012-13	Cum	3.78
6	580.80	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 167, Item No. 20.18) SR 12-13	Cum	1059.48

7	**3872.00**	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 172, Item No. 21.6) SR 12-13	**Sqm**	**39.64**
8	96.80	KSRRB M500-18. Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 174, Item No. 21.20.5) SR 12-13	**Cum**	**8992.08**
9	580.80	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	**Cum**	**72.71**

Signature of the Contractor
Reg. No.
Postal Address

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ ..... 2 ರಲ್ಲಿ
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಳ್ಳದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92

Executive Engineer
Byatarayanapura Divisi
BBMP, Bangalore - 92